

HORN TAVERN ROAD CULVERT REPLACEMENT QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY
105-01	CONSTRUCTION STAKES, LINES AND GRADES	LS	1
201-01	CLEARING AND GRUBBING	LS	1
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	1
202-03.01	REMOVAL OF ASPHALT PAVEMENT	S.Y.	137
203-20.01	CHANNEL SUBSTRATE	C.Y.	4
209-09.01	SANDBAGS	LS	1
209-09.03	SEDIMENT FILTER BAG (15' X 15')	EACH	1
209-99.91 ¹	EROSION CONTROL	LS	1
303-01.01	GRANULAR BACKFILL (ROADWAY)	TON	215
303-10.01	MINERAL AGGREGATE (SIZE 57)	TON	20
307-02.01	ASPHALT CONCRETE MIX (PG 70-22) (BPMB-HM) (GRADING A)	TON	12
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) (GRADING B-M2)	TON	8
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	TON	0.20
402-02	AGGREGATE FOR COVER MATERIAL (PC)	TON	1
403-02.01	TRACKLESS TACK COAT	TON	1
411-02.10	ACS MIX (PG70-22) GRADING D	TON	7
604-02.01 ²	CLASS A CONCRETE	C.Y.	25
604-03.02 ³	STEEL BAR REINFORCEMENT	LB.	4688
712-01	TRAFFIC CONTROL	LS	1
712-05.01	WARNING LIGHTS (TYPE A)	EACH	5
712-06	SIGNS (CONSTRUCTION)	S.F.	136
712-07.03	TEMPORARY BARRICADES (TYPE III)	L.F.	84
713-02	TYPE III OBJECT MARKER	S.F.	12
713-06	STEEL WF-BEAM (BREAKAWAY) SIGN SUPPORT	L.F.	42
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	L.M.	0.05
717-01	MOBILIZATION	LS	1
740-11.03	TEMPORARY SEDIMENT TUBE 18 INCH	L.F.	1
801-01	SEEDING (WITH MULCH)	UNIT	1

HORN TAVERN ROAD CULVERT REPLACEMENT QUANTITIES			
ITEM NO.	DESCRIPTION	UNIT	QUANTITY
801-01.07	TEMPORARY SEEDING (WITH MULCH)	UNIT	1
801-03	WATER (SEEDING)	M.G.	0.1
801-07	SEED (SUPPLEMENTAL APPLICATION)	LB.	5
801-08	FERTILIZER (SUPPLEMENTAL APPLICATION)	TON	1
805-12.04 ⁴	EROSION CONTROL BLANKET (TYPE IV) BIODEGRADABLE	S.Y.	18
	UTILITY RELOCATION	LS	1

¹TO INCLUDE PUMP AROUND AND OTHER MISCELLANEOUS ITEMS

²ALL POUR-IN-PLACE STRUCTURES MUST BE INSTALLED IN ACCORDANCE WITH TDOT SPECIAL PROVISION SP502C. CONTRACTOR MAY PROPOSE ALTERNATE TO POUR-IN-PLACE STRUCTURES; ALL ALTERNATE PROPOSALS MUST BE SUBMITTED TO THE CITY FOR REVIEW AND APPROVAL BY THE ENGINEER (19 C.Y. CULVERT, 6 C.Y. WINGWALLS)

³(3774 LB CULVERT, 914 LB WINGWALLS)

⁴TYPE IV EROSION CONTROL BLANKET MUST BE BIODEGRADABLE